

DIESEL BUND LINING

We were awarded the project of refurbishing and applying a lining system to numerous sites for a regional water authority.

The bund pictured was a large bund of 631m² with several tank support plinths.



The bund was cleaned and then grit-blasted to ensure an excellent bond would be achieved between the substrate and the lining system.

A 3mm GRP (glass reinforced plastic) lining system was applied to the bund and plinths to ensure it would be strong, seamless, hard wearing and long lasting.



It was determined that once lined a bund of this size would obviously retain a large amount of rain water. Due to this fact a Bundguard was installed to remove water without human intervention.

By eradicating the need for manual water removal from the bund and associated costs, the Bundguard system will pay for itself within six months.